Advanced Structural Repair, LLC PO BOX 3185 Cary, NC 27519 US (919) 377-0796 drewv@advancedsr.com



Estimate

	ADDRESS Adam and Kristina Heinz 103 Wood trail Ln Cary, NC 27518			SHIP TO Adam and Kristina Heinz 103 Wood trail Ln Cary, NC 27518			
ESTIMATE #		DATE					
4405		01/28/2022					

DATE	ACTIVITY	QTY	RATE	AMOUNT
	Jack and Shim Jack and Shim - Jack, level, and re-shim the existing timber floor beam. This work will include running a string-line along the existing beam framing in the crawlspace as well as checking floor levels from above during the jacking operation and will be completed in a thoughtful manner to address any interior areas of concern.	1	2,100.00	2,100.00
	05 Masonry Masonry - Install supplement floor pier supports along the main floor girder; use 5 new supplemental floor piers installed between existing floor pier locations. Piers to be 8-inch by 16-inch CMU floor piers (filled solid) on 16-inch by 24-inch by 8-inch cast in place footers.	5	650.00	3,250.00
	Plans and Permits:01.2 Building Permits Building Permits	1	375.00	375.00
Please note: Payment is due upon completion of the job. TOTAL		\$5,725.00		

Accepted By

Accepted Date

If you have any questions feel free to contact any of us at the following: